BRIGHT HERMOSA BUILDERS INC.	Document No.	Section No.
	Effective Date:	Revision No.
	PROCEDURAL MANUAL	
	DESIGN AND PLANNING (EXTERNAL CLIENT)	

OBJECTIVE	This procedure shows the process from the project initiation up to the preparation of construction drawings
SCOPE	This procedure includes the process for the design and planning for external clients

Responsibility	Activities		Documents
Design Engineering Team Client	Project Initiation and Client Briefing	Note 1	-
Design Engineering Team	Site Analysis and Feasibility Study	Note 1	-
Design Engineering Team	Conceptual Design		-
Client	Approved?	NO / YES	
Design Engineering Team	Schematic Design		
Client	Approved?	NO / YES	
Design Engineering Team Client	Design Development		
Design Engineering Team Client	Construction Documents		

1**. Project Initiation and Client Briefing**

- Client Consultation:
  a. Meet with the client to understand their vision, needs, and project objectives.
  b. Gather information on site location, budget, timeline, and any specific requirements.
  c. Discuss potential design concepts and aesthetic preferences.
- Project Definition:
  a. Define the project scope, including the type of structure (residential, commercial, industrial), size, and intended use.
  b. Identify key stakeholders and their roles in the project.
  c. Establish clear communication channels and project management protocols.

2. Site Analysis and Feasibility Study

- Site Investigation:
  a. Conduct a thorough site visit to assess the existing conditions, including topography, soil conditions, vegetation, access points, and utilities.
  b. Obtain necessary permits and clearances for site investigation and surveying.
- Feasibility Study:
  a. Analyze the site's suitability for the proposed development, considering zoning regulations, environmental constraints, and potential risks.
  b. Assess the availability and capacity of utilities and infrastructure.
  c. Evaluate the project's financial feasibility and potential return on investment.

3. Conceptual Design

- Concept Development:
  a. Based on the client's brief and site analysis, develop initial design concepts and explore different options.
  b. Consider the project's functionality, aesthetics, sustainability, and compliance with local building codes and regulations.
- Client Presentation:
  a. Present the conceptual designs to the client, explaining the rationale behind each option.
  b. Gather feedback and refine the designs based on the client's preferences.

4. Schematic Design

- Schematic Drawings:
  a. Develop schematic drawings that illustrate the overall layout, spatial relationships, and major design elements of the project.
  b. Include floor plans, elevations, sections, and 3D visualizations.
- Preliminary Engineering:
  a. Conduct preliminary structural, MEPFS (mechanical, electrical, plumbing and fire safety), and other engineering analyses to ensure the design's feasibility and safety.
- Client Approval:
  a. Obtain the client's approval on the schematic design before proceeding to the next phase.

5. Design Development

- Detailed Design:
  a. Refine the schematic design into more detailed construction drawings and specifications.
  b. Coordinate with various consultants (structural, MEP, landscape, etc.) to integrate their designs into the overall project.
  c. Prepare detailed material and finish selections.
- Cost Estimation:
  a. Develop a detailed cost estimate based on the design development drawings and specifications.
  b. Review and refine the estimate with the client to ensure it aligns with their budget.

6. Construction Documents

- Construction Drawings and Specifications:
  a. Prepare final construction drawings and specifications that provide clear and comprehensive instructions for contractors and builders.
  b. Ensure compliance with all applicable building codes, regulations, and standards (e.g., the National Building Code of the Philippines).
- Permitting and Approvals:
  a. Submit construction documents to the relevant government agencies (e.g., the local building official) for review and approval.
  b. Obtain necessary permits and clearances before construction can commence.

Additional Considerations

- Collaboration and Communication: Foster effective collaboration and communication among all project stakeholders, including the client, design team, consultants, and contractors.
- Sustainability: Integrate sustainable design principles and practices into the project, considering energy efficiency, water conservation, and the use of eco-friendly materials.

Prepared by:	Reviewed by:	Recommending Approval by:	Approved by:
Marcone John Perea *Office Engineer*	**Mark Anthony Pajes** *Project Engineer*	**Nemesia P. Baylon** *Development Director*	**Adrian Carlo Escay** *President & CEO*