	Document No.	Section No.
	Effective Date:	Revision No.
	PROCEDURAL MANUAL	
	PROJECT EXECUTION & PRODUCTIVITY TRACKING PROCEDURE	

OBJECTIVE	To establish a rigorous, manual system for planning and monitoring construction activities. The focus is on ensuring that **Critical Path** activities are prioritized and that individual worker productivity is documented and verified to meet project deadlines.
SCOPE	This procedure applies to all on-site construction activities performed by BHBI personnel and subcontractors. It governs the transition from high-level scheduling to daily site execution.

Responsibilities

- **Project Engineer : Primary owner of the Critical Path Method (CPM). Responsible for identifying the Critical Path from the Master Schedule, highlighting "Red Line" activities, and managing the Critical Path Tracking & Variance Report [T-CPM-001].**
-
- **Site Engineer : Leads the technical execution, monitors daily worker output, and prepares the Daily Worker Productivity Log [T-DWP-001].**
-
- **Assistant Project Engineer): Performs on-site physical verification of reported work to ensure actual progress matches the Site Engineer's logs.**
-
- **Office Engineer : Records the Toolbox Meeting Minutes [T-TBM-001], performs mathematical verification of productivity logs**

Planning & The 3-Week Look-Ahead (3WLA)

1. **Scheduling:** The 3WLA session shall be convened at a date and time determined by the Project Manager or Project Engineer. The frequency shall be sufficient to ensure a continuous 3-week planning horizon is maintained.
2. **Identification:** During the session, the PE and SE shall extract the next three weeks of activities from the Master Schedule.
3. **Critical Path Focus:** Activities on the **Critical Path** must be highlighted in **Red**.
4. **Make-Ready Check:** The SE must verify that all materials, tools, and permits for "Red Line" tasks are physically confirmed for the upcoming weeks.

4.2. Bi-Weekly Toolbox & Activity Briefing

- **Monday Schedule:** The SE briefs the crew on the week's targets, focusing on Critical Path tasks.
- **Thursday Schedule** The SE reviews progress from Mon–Wed. If a Critical Path task is lagging, the SE reassigns workers from "Float" (non-critical) tasks to ensure completion by Saturday.

4.3. Daily Worker Productivity Tracking

1. The SE shall monitor each worker/gang throughout the day.
2. The SE prepares the **Daily Worker Productivity Log [T-DWP-001]**, recording the specific location, task, and actual output quantity for every individual worker.
3. **Priority Rule:** The SE must verify the output of workers on Critical Path tasks first.

4.4. Counter-Checking & Verification (The Audit)

1. At the end of each day, the SE submits the log to the APE or OE.
2. The APE performs a physical spot-check on-site to confirm the reported quantities.
3. The OE verifies that the quantities are within the budget scope.
4. The APE/OE counter-signs the log. Only signed logs are considered official progress.

4.5. Critical Path Monitoring (Separate Document)

1. If a Critical Path task is delayed, the APE prepares the **Critical Path Tracking & Variance Report [T-CPM-001]**.

2. This document must identify the "Root Cause" and a "Catch-Up Plan" (e.g., overtime or additional manpower).

5. DOCUMENTATION & DELIVERABLES

Document Code	Document Name	Frequency	Responsible
T-3WLA-001	3-Week Look-Ahead	As Determined	Project Engineer
T-DWP-001	Daily Worker Productivity Log	Daily	Site Engineer
T-CPM-001	Critical Path Status & Variance	On Delay	Asst. Project Engineer
T-TBM-001	Toolbox Meeting Minutes	Mon / Thu	**Office Engineer**

1. Week 1: The "Execution" Week (Current)

- **Goal:** Execution of the work.
- **Action:** The site engineer utilizes the **Daily Worker Productivity Log**. The targets were set during the Toolbox meeting.

2. Week 2: The "Coordination" Week (Next Week)

- **Goal:** Advance preparation for the following week.
- **Action:** You check if the materials from your **Material Management Manual** are actually on-site.

3. Week 3: The "Constraint" Week (Horizon)

- **Goal:** Remove "Blockers."
- **Action:** You look for things that take a long time to fix.

Prepared by:	Reviewed by:	Approved by:	Noted by:
Marcone John Perea *Office Engineer*	**Mark Anthony Pajes** *Project Engineer*	**Nemesia P. Baylon** *Development Director*	**Adrian Carlo Escay** *President & CEO*