BRIGHT HERMOSA BUILDERS INC.	Document No.	Section No.
	Effective Date:	Revision No.
	PROCEDURAL MANUAL	
	PROJECT INSPECTION AND TURN-OVER	

OBJECTIVE	To ensure that completed projects meet customer requirements.
SCOPE	This procedure covers activities from the submission of a request for preliminary inspection to the turnover of completed projects to customer.

Responsibility	Activities		Documents
Contractor	Submit Letter of Request for Inspection	Note 1	*Letter Request of Letter for Inspection Accomplishment Report*
Project Engineer/ Quality Control Site Engineer	Conduct Joint Site Inspection	Note 2	*Specifications & Drawing Registry Plans Punch List*
Quality Control	Issue Punch Listing	Note 3	*Punch Listing*
Contractor	Repair Defective Works		*Punch Listing*
Project Engineer/ Quality Control	Inspection of Repaired Defective Works	Note 4	*Specifications & Drawing Registry Plans Punch Listing*
	Repaired?	NO / YES	
Project Engineer/ Quality Control	Conduct Final Inspection		*Specifications & Drawing Registry Plans Punch Listing*
Project Engineer	Certification of Turn-Over and Acceptance	Note 5	*Certification of Acceptance*
Project Engineer	Turn Over		*Project Completion Report*

NOTE 1: [Submit Letter of Request for Inspection]

1. Letters of Request for Inspection must only be submitted after the retention period has passed.

NOTE 2: [Conduct Joint Site Inspection]

1. Evaluate and review the readiness based on the Accomplishment Reports.
2. Conduct a Walkthrough with the Contractor on project site for the Joint Site inspection.
3. Take pictures as a proof of defective work to be repaired.

NOTE 3: [Issue Punch Listing]

1. Prepare a punch listing based on the inspected quality assurance of the activities.
2. Attach pictures of the defective work and map out to the Punch List.
3. Issue a Punch List to the Contractor to identify the defective works.
4. Set a Coordination Meeting with Contractor to discuss about the listed Defective Works on the Punch List, to have collaboration on identifying what are the methods to be used in repairing the defectives to still provide a good quality of work.

NOTE 4: [Inspection of Repaired Defective Works]

1. Evaluate and review the readiness based on the Punch List.
2. Conduct a Walkthrough with the Contractor for a Joint Site Inspection to check that all listed defective work has been repaired completely
3. If repaired, conduct a Final Inspection for Issuance of Certificate of Acceptance and to finally approve the Turn-Over of the project.
4. If not yet repaired, issue again a Punch List of the remaining defective works that needs to be repaired.

NOTE 5: [Certification of Turn-Over and Acceptance]

1. If the Contractor passed on the Final Inspection, a Certificate of Acceptance shall be issued by the Client.
2. Issue a Certificate of Acceptance to formally and to legally certify that the project has been accepted by the Client and ready for turn-over to the Client.

RECORDS GENERATED:

1. Letter Request of Letter for Inspection
2. Punch List
3. Certificate of Acceptance

REFERENCES:

1. Accomplishment Report
2. Specifications & Drawing Registry Plans

Prepared by:	Reviewed by:	Recommending Approval by:	Approved by:
		Nemesia P. Baylon *Development Director*	**Adrian Carlo Escay** *President & CEO*