VHBC Building Leisure Lifestyle Communities	Document No.	Section No.
	Effective Date:	Revision No.
	PROCEDURAL MANUAL	
	QUALITY ASSURANCE & CONTROL	

OBJECTIVE	Ensure that the construction project meets the specified quality standards, complies with contractual requirements, and satisfies client expectations.
SCOPE	This procedure includes the process for ensuring the quality of the deliverables for each project

Responsibility	Activities		Documents
-	Assign QA/QC Team Members	Note 1	-
-	Develop QA/QC Plan	Note 1	*Approved QA/QC Plan*
	Pre-Construction Meeting		*Minutes of the Meeting*
-	Inspect Incoming Materials	Note 1	*Material Inspection Report*
	Periodic On-Site Inspection		*Daily & Weekly Inspection Report*
	Log Non-Conformance Issues		*Non- Conformance Report* *Resolution Records*
	Prepare QA/QC Reports		*Periodic QA/QC Reports*
	Conduct Final Inspection		*Final Inspection Report* *Punchlisting Documentation*
	Obtain Client-Sign Off		*Certificate of Acceptance*
	Maintain QA/QC Records		

1. [Assign QA/QC Team Members]

a. Identify experienced personnel to form the QA/QC team. This may include a QA/QC manager, inspectors, and document controllers.
b. Define roles and responsibilities. For instance: QA/QC Manager oversees the implementation of the QA/QC plan. Inspectors handle on-site inspections. Document controllers maintain records of quality reports.
c. Train the team on the project's specific quality requirements.

2. [Develop QA/QC Plan]

a. Review the project specifications, drawings, and contract documents to determine quality standards.
b. Define benchmarks for key activities, such as concrete strength, rebar placement tolerances, and welding standards.
c. Outline inspection schedules (e.g., daily, weekly, or milestone-based).
d. Include procedures for handling non-conformance, material testing, and documentation.

3. [Conduct Pre-Construction Meeting]

a. Schedule a meeting with the project team, contractors, and subcontractors.
b. Discuss quality expectations, inspection schedules, and reporting procedures.
c. Provide a checklist of quality deliverables (e.g., material certificates, test reports).
d. Resolve any questions or concerns before construction begins.

4. [Inspect Incoming Materials]

a. Step 1: Verify the specifications of materials upon delivery (e.g., cement grade, steel diameter).
b. Step 2: Check manufacturer's certificates, test reports, and compliance documents.
c. Step 3: Reject and document non-conforming materials, notifying suppliers immediately.
d. Step 4: Label approved materials for proper identification and storage.

5. [Perform Periodic On-Site Inspections]

a. Conduct inspections during each phase of construction (e.g., foundation, superstructure, finishes).
b. Use checklists to ensure compliance with specifications and standards.
c. Take photographs and detailed notes to document site conditions.
d. Coordinate with subcontractors to address deficiencies immediately.

.

6. [Log Non-Conformance Issues]

a. Record any deviations from the quality plan or specifications.
b. Issue a Non-Conformance Report (NCR) to the responsible party.
c. Propose corrective actions and set deadlines for resolution.
d. Verify that corrective actions have been implemented and documented.

7. [Prepare QA/QC Reports]

a. Compile daily or weekly QA/QC reports summarizing inspections, test results, and observations.
b. Highlight key findings, including approved and rejected materials, completed inspections, and resolved NCRs.
c. Share the reports with stakeholders (e.g., project manager, client).

8. [Conduct Final Inspection]

a. Review the completed work against project specifications and the QA/QC checklist.
b. Conduct testing and validation for critical systems (e.g., water pressure testing for plumbing, electrical continuity testing).
c. Identify and document any punch list items for correction.
d. Ensure all punch list items are resolved before turnover.

9. [Obtain Client Sign-Off]

a. Present the final QA/QC documentation, including inspection records, material test results, and the completed punch list.
b. Conduct a walkthrough of the project site with the client.
c. Address any final concerns raised by the client.
d. Obtain formal acceptance and sign-off from the client.

10. [Maintain QA/QC Records]

a. Archive all QA/QC documents, including reports, NCRs, test results, and certificates.
b. Organize the records in a secure system for easy retrieval.
c. Retain records for the legally required duration or per the contract terms.

Records Generated

- QA/QC Plan
- Minutes of the meeting
- Material Inspection Report
- Daily & Weekly Inspection Report
- Non conformance report
- Final Inspection Report
- Punchlisitng Documentation
- Certificate of Accepta

Prepared by:	Reviewed by:	Approved by:	Noted by:
Marcone John Perea *Office Engineer*	**Mark Anthony Pajes** *Project Engineer*	**Nemesia P. Baylon** *Development Director*	**Adrian Carlo Escay** *President & CEO*