	Document No.	Section No.
	Effective Date:	Revision No.
	PROCEDURAL MANUAL	
	WATER SUPPLY CONNECTION PROCEDURE	

OBJECTIVE	To provide a standardized process for Lot Owners to apply for a water service connection and to ensure that the installation of meters and piping adheres to BHBI technical standards using the site's Deepwell and Water Tank system.
SCOPE	This procedure covers the application, payment, material preparation, and physical installation of water meters and service lines for residential lots within the Eastwest Breeze Leisure Farm project.

Responsibilities

- **Office Engineer (OE): Responsible for receiving applications, verifying lot ownership, and issuing the Payment Slip.**
- **Site Engineer (SE): Responsible for scheduling the installation, inspecting the connection point, and preparing the Material Withdrawal Slip for the connection kit.**
- **Plumber / Site Worker: Responsible for the physical tapping of the main line and installation of the NWRB calibrated meter.**
- **Project Engineer (PE): Responsible for final inspection and "As-Built" documentation to ensure the connection is recorded on the site utility map.**

PROCEDURE

4.1. Application and Payment

1. Submission: The Lot Owner submits a "Water Connection Request Form" to the Office Engineer.
2. Verification: The OE verifies that the lot is ready for connection and is within the service area of the project's Deepwell/Water Tank system.
3. Payment: The admin issues a payment instruction for the Connection Fee of ₱3,500.00.
    - *Note: This fee covers labor, piping materials, and the NWRB calibrated water meter.*
4. Acknowledgment: Once payment is confirmed, the OE forwards the approved application to the Site Engineer for scheduling.

4.2. Material Preparation

1. The admin prepares the standard "Connection Kit" which includes:
    - One (1) NWRB Calibrated Water Meter.
    - Required length of HDPE or blue PPR pipes.
    - Fittings (Elbows, Tee, Male/Female Adaptors, and Ball Valve).
    - Teflon tape and sealant.
2. The SE must cross-reference this with the Material Management Procedure to ensure inventory levels are maintained.

4.3. Installation Process

1. Marking: The site engineer and Plumber locate the tapping point on the main water line fronting the specific lot.
2. Tapping: The main line is tapped using a Service Saddle Clamp.
3. Meter Setting: The NWRB Calibrated Meter must be installed in a visible, accessible area near the lot boundary for easy monthly reading.
4. Testing: The system is pressurized to check for leaks at the joints.

4.4. Documentation and Handover

1. Reading: The Plumber records the "Initial Reading" (usually 0000) on the installation report.
2. Final Sign-off: The SE and the Lot Owner (or representative) sign the Completion Report.
3. As-Built: The OE updates the Project Master Plan to show that the specific lot is now "Active" for water billing.

---

5. TECHNICAL SPECIFICATIONS

- Source: Project Deepwell & Elevated Water Tank.
- Meter Type: NWRB Calibrated (Standard Residential Size).
- Connection Fee: ₱3,500.00 (Inclusive of all materials and labor).

Prepared by:	Reviewed by:	Approved by:	Noted by:
Marcone John Perea *Office Engineer*	**Rhenz Dela Cruz** *Project Engineer*	**Nemesia P. Baylon** *Development Director*	**Adrian Carlo Escay** *President & CEO*